

PRIOR TO INSTALLATION

- DO store cartons horizontally on a smooth, solid, flat, clean surface.
- DO NOT store the cartons directly on concrete, allow for air circulation. Concrete Floor can be up to 10° F Colder than ambient room temperature.
- DO NOT stack higher than ten cartons.
- DO NOT stack anything on top of uninstalled Homestead JetCore™ XL Flooring.
- DO maintain a minimum of 55° degrees F and maximum of 85° F before, during and after installation.
- DO carefully check flooring material for any defects. Contact your supplier immediately if any defect is found.
- DO be sure to install all base and island kitchen cabinets prior to installing the Homestead JetCore XL.
- DO NOT install base cabinets or island cabinets on top of the floor.
- DO Remove all furniture and appliances from the room, as well as existing quarter round, baseboard molding or cove base.
- DO Undercut doorway moldings to be the thickness of the flooring.
- DO Be sure to read through all of the installation instructions and warranty information before starting the installation.
- DO NOT install your Homestead JetCore XL over soft subfloors such as carpet. This product is recommended for INDOOR use ONLY.
- DO prepare existing subfloor according to the instruction below. Failure to do so will void the manufacturer's warranty.
- DO NOT install this product over any subfloor with non-embedded radiant heat. (Please see section on radiant heat).

WARRANTY NOTE

PLEASE EXAMINE FLOORING FOR COLOR AND QUALITY BEFORE INSTALLATION. OUT FLOORING IS MANUFACTURED IN ACCORDANCE WITH INDUSTRY STANDARDS. IF MATERIAL IS OF UNSATISFACTORY QUALITY, PLEASE CONTACT THE SELLER IMMEDIATELY. UNDESIRABLE PIECES SHOULD NOT BE INSTALLED. FLOORING WARRANTIES DO NOT COVER MATERIAL WITH VISIBLE DEFECTS ONCE THEY ARE INSTALLED. THE ORIGINAL PURCHASER OF THE FLOORING IS RESPONSIBLE FOR FINAL INSPECTION OF FLOORING QUALITY AND GRADE. ANY EXCESS FLOORING SHOULD BE STORED IN A CLIMATE-CONTROLLED AREA FOR REPAIRS IN THE EVENT OF FUTURE DAMAGE.

ASBESTOS WARNING!

WARNING! EXISTING RESILIENT FLOORING MAY CONTAIN ASBESTOS FIBERS OR CRYSTALLINE SILICA. DO NOT SAND, DRY SCRAPE, DRILL, SAW, BEAD BLAST OR MECHANICALLY CHIP OR PULVERIZE ANY EXISTING RESILIENT FLOORING, BACKING, LINING FELT, OR ASPHALTIC "CUTBACK" ADHESIVE. AVOID CREATING DUST. INHALATION OF SUCH DUST IS A CANCER AND RESPIRATORY TRACT HAZARD. SMOKING BY INDIVIDUALS EXPOSED TO ASBESTOS FIBERS GREATLY INCREASED THE RISK OF SERIOUS BODILY HARM. UNLESS POSITIVELY CERTAIN THAT THE EXISTING PRODUCT IS A NON-ASBESTOS CONTAINING MATERIAL, YOU MUST PRESUME IT CONTAINS ASBESTOS. REGULATIONS MAY REQUIRE THAT THE MATERIAL BE TESTED TO DETERMINE ASBESTOS CONTENT. SEE THE CURRENT EDITION OF RESILIENT FLOOR COVERING INSTITUTE (RFCI) PUBLICATION "RECOMMENDED WORK PRACTICES FOR REMOVAL OF RESILIENT FLOOR COVERINGS" FOR DETAILED INFORMATION AND INSTRUCTION ON REMOVING ALL RESILIENT COVERING STRUCTURES.

THIS HOMESTEAD JETCORE XL DOES NOT CONTAIN HAZARDOUS MATERIALS SUCH AS ASBESTOS OR CRYSTALLINE

SUITABLE SUBSTRATES AND SURFACE MATERIALS

CONCRETE SUBSTRATES

- Homestead JetCore XL may be installed over on grade, above grade, or below grade concrete subfloors. A 6mil polyethylene moisture barrier MUST be used with concrete subfloors.
- Concrete must be permanently dry, clean, smooth, level, and free from all foreign materials such as dust, wax, glues, solvents, paints, grease, oils, and any chemical residues.
- New and existing concrete subfloors MUST meet the guidelines of the latest edition of ASTM F 2170 and ASTM 1869, "Standard Practice for Preparing Concrete Floors to Receive Resilient Flooring" available from the American Society for Testing and Materials, 100 Barr Harbor Drive, West Conshohocken, PA 19428; (610) 832-9585; <u>http://www.astm.org/</u>
- Concrete shall be finished and cured according to ACI and have a minimum compressive strength of 3500 psi.
 Installation of moisture barrier is recommended prior to pouring out on or below grade slabs. A 6mil polyethylene moisture barrier MUST be used with concrete subfloors. Moisture vapor transmission shall not exceed 8 lbs./1000 sq. ft./24 hours per ASTM F-1869 (Anhydrous Calcium Chloride Test). Moisture levels must also be tested according to ASTM F-2170 (American Standard Test Method for determining relative humidity in concrete floor slabs using in site probes). When testing according to this method, the internal relative humidity shall not exceed 85%. Homestead JetCore XL may be installed over gypsum-based underlayment's.
- Holes, grooves, expansion joints and other depressions must be filled with a Portland based patching and leveling product, and troweled smooth and feathered even with the surrounding surface.
- Maximum acceptable pH levels of 9 or less. Refer to Resilient Floor Covering Institute Website at: https://rfci.com/recommended-work-practices/
- DO NOT install over concrete with a history of high moisture or hydrostatic conditions.

EXISTING FLOORS

Homestead JetCore XL may be installed over most smooth, single layer, hard surface existing flooring (resilient, tile, ceramic, marble, and terrazzo). Existing flooring must be moisture free and in good condition. Any residue (i.e. old glue) on subfloor must be completely removed. Check flooring for any curled areas around the perimeter or at seams and repair if necessary. Level by using a good quality cementitious based embossing leveler to smooth and fill the existing floor or grout lines. Tile may require several skim coats to achieve a flat surface.

WOOD SUBSTRATES

- Wood floors must be double constructed with a minimum thickness of 1" inch, free from spring/deflection. Top layer of plywood shall be ¼" inch minimum thickness underlayment grade plywood. Recommended underlayment's include APA Underlayment Grade Plywood: A-C, B-C, or C-C plugged, ACCUPLY, SurePly, TECPLY, ULAY, C.S.A. (CanPly) and ProBoard.
- DO NOT install material over wood subfloors that lay directly on concrete or over sleeper construction. All subfloors
 must be structurally sound and installed following their manufacturer's installation instructions. Local building codes
 may only establish minimum requirements of the flooring system and may not provide adequate rigidity and support
 for proper installation and performance.
- A moisture test is required using a pin-type moisture meter. The moisture content should be 13% or less.
- Joist Spacing should not exceed 19" inches. Use nail set for fasteners exposed above surface. Fill and sand gaps wider than 1/8" inch wide.
- If the surface of the wood subfloor is not smooth, a ¹/₄" inch underlayment panel must be installed over the subfloor, per the underlayment manufacturer's written instructions.
- Homestead JetCore XL[™] should NOT be installed directly over fire-retardant treated plywood or preservative treated plywood. An additional layer of APA rated ¼" inch thick underlayment is recommended as a buffer between the two

RADIANT HEAT

Homestead JetCore XL can be installed over radiant heat. Please read through these special instructions when using a radiant heating system under the Homestead JetCore XL before the flooring installation.

PLEASE NOTE WHEN USING RADIANT HEAT:

- The subfloor surface temperature must never exceed 80 degrees Fahrenheit throughout the life of the floor.
- Homestead JetCore XL should never come in direct contact with the radiant heating system.
- Use of an in-floor temperature sensor is recommended to avoid overheating.

RADIANT HEAT SPECIAL INSTRUCTIONS:

- 1. Completed Radiant Heat System must be operational for a minimum of two weeks.
- 2. Radiant heat components must have a minimum of 1/2" inch separation from the product.
- 3. Radiant Heat System should be turned off for 72 hours prior to installation of Homestead JetCore XL and remain off for 72 hours after the Systems installation is complete.
- After installation and 72-hour acclimation period, the radiant heat system can be turned on. We suggest to gradually increase the temperature in increments of 5°F to avoid overheating. Maximum operating temperature should never exceed 80° F.
- 5. Once this process is complete the Radiant Heat System can be used at its normal room temperature setting.
- 6. All other standard installations instructions apply.

BATHROOMS

When the Homestead JetCore XL is installed in a bathroom, the flooring can be laid under the toilet only if the floor is separated from adjacent rooms with a doorway threshold. Otherwise the flooring should be installed around the toilet leaving a 1/8" inch expansion space. Use a high-quality silicone caulking to fill the expansion space at the tub, shower and all wet areas to prevent surface water seepage under the floor.

STAIRS

Homestead JetCore XL can be installed when fully adhered over steps using a high quality pressure sensitive luxury vinyl

tile adhesive such as Franklin® 780. Follow the instructions on the adhesive for trowel size and drying time. Always use a

flush stair nose molding to finish each step at the nose.

PRODUCT RUN SPECIFICATION: THESE PLANKS CAN HAVE SLIGHT COLOR VARIATIONS BETWEEN PRODUCT RUNS. BEFORE STARTING THE INSTALLATION, IT IS BEST TO CHECK THE PRODUCT RUN NUMBER WHICH IS LOCATED ON THE LABEL ON THE SHORT SIDE (END) OF THE CARTON. IF YOU FIND THAT YOU HAVE CARTONS FROM DIFFERENT PRODUCTION RUNS, IT IS HIGHLY RECOMMENDED THAT YOU OPEN 3 - 4 CARTONS AND INSTALL A MIX OF PLANKS FROM EACH DIFFERENT PRODUCTION RUN ON YOUR FLOOR. THIS WILL RESULT IN A MORE NATURAL LOOKING FLOOR.





3. 1/4" SPACERS 4. T-SQUARE

EDGE

5. LONG STRAIGHT

.....



YouTube for

"Homestead Flooring

Installation"



PULL BAR

20-30° ANGLE

TONGUE SIDE 🔍

SNAPPING/PULL BAR ANGLE

FIGURE 5A

FIGURE 4

UNICLIC

GROOVE SIDE

GETTING STARTED

- Determine which direction the planks will be installed. To make the room appear larger or if installing in very small rooms or hallways, it is preferable to lay the planks parallel to the longest room dimension.
- Carefully measure the room to determine squareness and to determine the width of the last row of planks. If the width of the last row of planks is less than 2" inch (50mm), excluding the tongue, the width of the first row of planks will have to be cut accordingly.
- A minimum of 1/4" expansion space is required around the perimeter of the room and all vertical objects (i.e. pipes and fixtures).
- Inspect all planks for visible defects and damage before and during installation. DO NOT install damaged planks. The manufacturer will not accept responsibility for claims on flooring installed with obvious defects. During installation, inspect the groove area and remove any debris that may prevent proper assembly of planks.

INSTALLATION STEPS

- 1. Begin installation parallel to the long dimension of the room, preferably parallel with the light sources (windows & doors) (Refer to Figure 1). Snap a chalk line at the starting point to maintain alignment. Use planks mixed in from four or five cartons to achieve the ideal random pattern.
- 2. Install planks from the left side of the starting wall and work to the right side. If starting with a full width plank, the tongue must be removed (Refer to Figure 3). To trim planks, use a utility knife and a straight edge. Score the top surface of the plank, flex it downward to separate pieces. The tongue side of the plank always faces the starting wall. Place ¼" inch (8.2mm) spacers between the short and long side of the planks and the wall. Always position one spacer between the wall and where the planks join.
- 3. Be sure to maintain a ¹/₄" inch expansion space around all walls and vertical objects and maintain a random appearance by cycling patterns of boards. Offset end joints a minimum of 8" inch (20.3cm).
- 4. The end joints of the planks in the first row are assembled by inserting the tongue side into the groove side of the previous plank at a low 20-30° degree angle. Gradually lower the plank down flat, applying pressure inward and downward clicking and locking the end of the new plank into the end of the existing plank until the end joint closes. Ensuring that the planks are perfectly aligned. Install remaining full planks in the first row (Refer to Figure 4).
- 5. The last plank in the first row may need to be cut. Measure the distance between the wall and the surface of the last full plank. Subtract 5/16" inch (8.2mm) from this measurement to allow for the spacer. If this measurement is less than 8" inches (20.3cm) long. (Refer to Figure 1)
- 6. When installing the first plank-cutting cut off from the last or first plank in the first row may serve as the first or last plank in the second row provided it is at least 8" inches (20.3cm) long. Always stagger end joints from row to row a minimum of 8" inches (20.3cm) long. (Refer to Figure 1)
- 7. When installing the first plank of the second row, remember to place a ¼" inch spacer between the wall and the short side of the plank. Insert the long side tongue into the groove side of the plank in the first row at a low angle and lower flat to the substrate. Shift the plank down toward the end seam and slightly lift the previous plank in order to engage the end joints together.
- 8. Install the second plank of the second row. Position the long side of the second plank with the tongue side of the existing plank overlapping the groove of the planks in the previous row approximately 1/8" inch. Then, angle the end joint into the previous plank. Angle the plank down and gently push in until the plank locks into the previous row (Refer to Figure 2). Continue installing remaining planks in the second row.

IT IS VERY IMPORTANT TO MAKE SURE THAT THE FIRST TWO ROWS ARE STRAIGHT AND SQUARE, OR THIS WILL ADVERSELY AFFECT THE ENTIRE INSTALLATION. THE FIRST TWO ROWS ARE THE "INFRASTRUCTURE" FOR THE REST OF THE INSTALLATION. NOTE TO CHECK STRAIGHTNESS AND SQUARENESS REGULARLY. (REFER TO FIGURE 1)

9. Continue working from left to right, row by row, making sure to install the planks with the long side seam first, then slide back to drop the end joint into place. Tap the ends to ensure a tight fit.